



CENTER FOR
**WATERSHED
PROTECTION**


**The Long-Term Effects of
BMP Implementation on
Stream Channel Stability in
Urban Watersheds**

Lisa Fraley-McNeal, CWP
Byron Madigan, Carroll County
Deb Caraco, CWP
Sami Khan, CWP
Bill Stack, CWP

Chesapeake Bay Trust Pooled Monitoring Forum
June 18, 2026

Research Question

What is the effectiveness of stormwater best management practices (BMPs) at the catchment scale?



Hypotheses




H1: The implementation of BMPs retrofitted to meet Carroll County's sand filter design standard will modify the runoff response from the watershed (hydrograph) resulting in a reduction in the magnitude, duration, and frequency of erosive flow rates that meet and or exceed MDE performance standards for stream channel protection.

H2: The implementation of these BMPs will create hydraulic conditions that lead to self-recovery of channel stability.

- a. The bank erosion rate in treatment reaches will be lower than the control reaches due to reduction in magnitude, duration, and frequency in flows that contribute to bank erosion.
- b. The treatment reaches will be aggrading due to the reduction in magnitude, duration, and frequency in flows resulting in sediment deposition on the streambed.

H3: The implementation of these BMPs will decrease sediment loadings downstream because of reduced bank erosion rates.



Carroll County Sand Filter Design


Unique Design Characteristics

- No Riser - all design flows through sand control
- Drop Structures and Level Pipes
 - Turbulent to laminar flow
- Total Capture of 2 year storm, “difference in 10 year runoff volume”
 - Direct runoff difference – Meadow and Impervious
- Sand layer seeded w/ MDE mix
 - Prevents cracking/short circuiting of filter



Maintenance Center
7/21/2018 - 7/28/2018
9.92" Total Rain


- Inlet
- Outfall
- Cumulative Rainfall



Monitoring Locations

Pre-Treatment Monitoring
November 2016 – October 2017

Post-Treatment Monitoring
October 2018 – June 2026




Study Site	Treatment or Control	Drainage Area (ac)	Impervious Cover (%)	Study Reach Length (ft)	Existing BMP Type	Retrofit Type
Blue Ridge ¹	Treatment	33.6	26.9%	145	Retention	Sand Filter
Central MD SVC ¹	Treatment	91.7	31.3%	325	Detention	Sand Filter
Robert's Field ¹	Control	28.8	37.4%	157	Extended Detention	N/A
Shannon Run	Treatment	209	20%	366	Retention	Wet Pond
Piney Ridge	Control	91.1	36.1%	559	Retention	N/A

¹ Rain gauge located at site.

Ponds were originally designed for 2- and 10-year management. At the treatment sites, the ponds were retrofitted to provide channel protection volume.



Monitoring Methods



H1: Hydrology

Central Maryland Service Center Treatment Site

Central MD SVC (T) - Rainfall, Stage, and Discharge



Note: Negative stage values were excluded from the plot for visualization purposes.

H1: Hydrology

Flow Measurement and Calculations


Measurement Changes

- Additional barometric pressure transducers in late 2024
- 2 x-sections measured per reach (down from 3)

Re-Evaluate Stage-Discharge Curves

- Add new “Phase 2” data to initial stage-discharge curves.
- Do we need a new curve based on:
 - Additional observations (improvement), or
 - Channel geometry changes
 - Possible revised methodology for flows beyond the range of the curve.

Central MD SVC (T) - Rating Curve



Rating curve was constructed using Phase 1 discharge measurements.

H1: Hydrology

Preliminary Post-Pre Comparisons


Paired Watershed/ mBACI Approach

- Compared both Discharge and flow volume relationships between Control and Treatment Sites.
- In Phase 2, continued to add data to these evaluations.


Key questions:

- Does the improvement from Treatment sites persist over time?
- Do the new data strengthen or weaken the original conclusions?

Peak Discharge Comparison
Central Maryland vs Piney Ridge



Runoff Volume Comparison
Central Maryland vs Piney Ridge



H2: Geomorphology

Shannon Run (Treatment)

May 2025



November
2016




May 2020




H2: Geomorphology

Shannon Run (Treatment)



May 2025



August 2025
(after riser low-flow orifice clog)



June 2026

H2: Geomorphology

Control Sites



**Piney Ridge
May 2026**




**Robert's Field
July 2024**


H2: Geomorphology

Cross Section Surveys

Piney Ridge XS3 (C) Pretreatment



Piney Ridge XS3 (C) Posttreatment




H2: Geomorphology

Bank Erosion Rates – Cross-Sections

Pre- and Post-Treatment Bank Erosion Rates by Cross-Section

Each bar represents one cross-section; T = treatment, C = control

Analysis Period Pre-Treatment Post-Treatment




H2: Geomorphology

Bank Deposition Rates – Cross-Sections

Pre- and Post-Treatment Bank Deposition Rates by Cross-Section


Each bar represents one cross-section; T = treatment, C = control

Analysis Period Pre-Treatment Post-Treatment




H2: Geomorphology

Bank Erosion Rates – Bank Pins



H3: Load Estimation

BANCS Overestimates Erosion Rates



H3: Load Estimation

Study Site	BANCS		Monitoring Data		
	Pretreatment Total TSS Load ¹ (tons/yr)	Post-Treatment Total TSS Load ¹ (tons/yr)	Pretreatment TSS Load (tons/yr)	Post-Treatment TSS Load (tons/yr)	% of Total Bank Length with Representative Monitoring Location ²
Central MD SVC (T)	42.11	45.04	3.42	8.92	89.8%
Piney Ridge (C)	59.25	75.9	0.72	0.40	31.3%
Shannon Run (T)	54.49	56.54	11.06	7.35	52.5%
Robert's Field (C)	24.26	27.21	1.01	1.83	91.5%

¹The loads represent the total load at edge-of-stream without a sediment delivery factor or stream restoration efficiency applied as per the CBP stream restoration crediting protocols.

²Total bank length obtained from the top of bank survey from the longitudinal profile and includes both the left and right bank lines.

Additional Analyses to be Completed

- Comparison of longitudinal profiles pre/post treatment
- Complete channel change analysis (in addition to the bank erosion/deposition results presented today)
- Particle size distribution analysis
- Measured curve number comparison to the theoretical predevelopment, post development, and retrofit design curve numbers
- Channel Stability - frequency of bankfull flow exceedance before and after treatment
- Revise stage-discharge curves and storm event definitions for remaining sections and add all observed data to our hydrology analyses.
- Complete an analysis of the curve number for additional storm events.
- In Phase 1, we abandoned the Blue Ridge treatment site due to ongoing construction but now we have a (delayed) post-treatment data for this site.

Thoughts and Lessons Learned

- Geomorphic changes take a while to see. We didn't see some changes in Phase 1 that are now present.
- Methods for estimating streambank sediment load can significantly affect results.
- Importance of pond retrofit maintenance. Malfunctions can undo the treatment results as we saw with Shannon Run.
- Make sure you have a "backup" pressure transducer to avoid gaps in measurement.
- Initial assessments suggest that the practices continue to mitigate storm flows, and we will understand this in more detail as we look at more data.


Funding & Acknowledgments

This research was funded through the Pooled Monitoring Initiative (PMI), Restoration Research Program.

Award #20593 | Center for Watershed Protection | 2022 - 2026

The Pooled Monitoring Initiative funds applied science to advance restoration research for cumulative impacts, comparative effectiveness of stormwater practices, pollutants of emerging concern, and trade-offs with new research questions added annually.

<https://cbtrust.org/grants/restoration-research/>



Thanks to the Many Funders and Partners!



Thank You

Lisa Fraley-McNeal

Sr. Watershed & Stormwater
Research Specialist
lfm@cwpc.org

Byron Madigan

Water Resource Supervisor
bmadigan@carrollcountymd.gov

Bill Stack

Senior Advisor
bps@cwpc.org

Deb Caraco

Sr. Watershed Engineer
dsc@cwpc.org

Sami Towsif Khan

Water Resources Engineer
stk@cwpc.org

Translation Slides

What are the take home points?
What does this mean for me?

Translation Slides by Deborah J. Cappuccitti,
Maryland Department of the Environment

What are the take home points?

- All ponds provided 2 and 10-year peak control prior to retrofit
 - Peak control known to increase the duration and magnitude of erosive flows
- Observations after cp_v retrofit show evidence of stream recovery
- Recovery is difficult to quantify:
 - Time: Recovery is slow - need time to observe improvements
 - Not consistent: Other watershed factors influence conditions (examples where the control at Piney is showing better results than the retrofit at Central)
 - Limits of existing tools: BEHI/NBS data are not useful for predicting recovery
 - Erosion rates are significantly over-estimated when compared to actual field conditions
 - Need better regional curves data to support use of the “one” Hickey Run curve
 - Recovery is observed with bank pin data but it takes years to get this data

What does this mean for me?

What do I take from this if I am a practitioner:

- Need for better regional curve data – to provide more accurate estimates of erosion rates to help predict channel recovery
- Better regional curve data can help improve accuracy for stream restoration crediting

What do I take from this if I am a regulator:

- Results show promise for future MS4 crediting. Need additional data to better understand applicability.
- In the meantime: Field data showing pollutant load reductions may justify a site-specific credit (i.e. Shannon Run)